

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20,313-0000

LEASE NAME Stueder

WELL NUMBER #5

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 29 TWP. 26 RGE. 12 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 7-29-92

Plugging Completed 8-17-92

LEASE OPERATOR Hellar Drilling Co, Inc.

ADDRESS 125 N. Market, #1422 Wichita, Ks. 67202

PHONE# (316-267-2845) OPERATORS LICENSE NO. 5015

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-13-92 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3193'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	293'	None
				7"	3192'	1616.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3080' & 6 sacks cement. Shot casing at 1800', 1700' & 1600'. Pulled 62 jts. of 7" casing. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks 60/40 pozmix cement with 6% gel, 10 sacks gel, 100# hulls, 10-3/4" plug and 150 sacks cement. Maximum pressure was 150 psi and shutin 50 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hellar Drilling Co, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold


James W. Rockhold
STATE CORPORATION COMMISSION

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1992

CONSERVATION DIVISION

My Commission Expires: _____



Notary Wichita, Kansas

8-18-92

15-151-20313-0000
CONTRACTOR'S WELL LOG

OPERATOR: Earl M, Knighton
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: STUEDER #5
LOCATION: NW NW SW Section 29-26S-12W
Pratt County, Kansas
SPUD DATE: January 4, 1976
COMPLETION DATE: January 14, 1976

0	290	Surface clay
290	2550	Shale
2550	3088	Shale & Lime
3088	3118	Lime & Shale
3118	3195	Shale & Lime
	3195	Rotary Total Depth

Drilled 293' of 12 3/4" hole. Set 11 jts. of 10 3/4" surface, Set @ 293'. Cemented with 210 sx. Common Cement, 3% ca. cl., 2% gel. Cement circulated. Plug was down @ 2:30 a.m. January 4, 1976.

Ran 130 jts. 7" pipe. Tallied 3196.35'. Set @ 3194'. Cemented with 250 sx. Cement. Plug was down @ 6:30 p.m. January 14, 1976.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr-Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the STUEDER #5, NW NW SW Section 29-26S-12W, Pratt County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of January 16, 1976.

Sandra Richman
Sandra Richman - Notary Public



STUEDER #5
15-151-20313-0000