

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1966

11-14-66

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shell Oil Company

Complete Address: 1200 First National Bldg., Oklahoma City, Oklahoma

Lease Name O. H. Hoeme Well No. # 4

Location SW NE NW Sec. 28 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4305'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:15PM Day 11th Month Nov. Year 1966

The Above well was plugged as follows:

795' of 8 5/8" surface pipe, cemented with 400 sacks. 4293' of 4 1/2" long
string, cemented with 600 sacks. Cast iron plug and 1 sack of cement was
set at 3800'. Top perferation 3694'. All perferations were squeezed with 100
sacks of cement with the top of the cement at 2530'. 13 sacks of Gel-Mud was
pumped in the hole to circulate and keep full. 1830' of 4 1/2" long string was
recovered from the hole. 22 sacks of Gel-Mud and 100 sacks of cement was
was pumped in to the surface pipe, through an 8 5/8" swage to a pressure of
400 lbs., bringing the cement to the base of the cellar. This cementing was
done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 11/15/66

INV. NO. 4290-W