

KANSAS

el STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Skelly Oil Co.

Complete Address 1860 Lincoln St. Denver, Co. 80203

Lease Name Cunningham B-Unit Well No. 51

Location C W/2 NW/NE Sec. 36 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 3501

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:30 AM Day 30 Month 5 Year 1970

The above well was plugged as follows:

356 ft of 8 5/8 surface pipe cemented with 125 sacks. 3447 ft of
5 1/2 long string cemented with 225 sacks. Sand back to 3430 ft. 10,
sacks cement with bailer. Mud to 350 ft, 10 ft, rock bridge, 25 sacks
cement. Mud to 40 ft, 10 ft rock bridge, 10 sacks cement to base of
cellar. Pulled 1700 ft. of 5 1/2.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell E. ...*
Well Plugging Supervisor

DATE 6/1/70
INV. NO. 1967-11