

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1967

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued April 13, 1967.Operator's Full Name Skelly Oil CompanyComplete Address: P. O. Box 649, McCook, Nebraska 69001Lease Name Cunningham "B" Unit Well No. # 58Location C N/2 SW NW Sec. 36 Twp. 27 Rge. 11 (E) (W) WCounty Pratt Total Depth 3720'Abandoned Oil Well Gas Well Input Well X SWD Well D & AOther well as hereafter indicated: Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.Address: Stafford, Kansas License No. 490Operation Completed: Hour 9:30AM Day 19th Month May Year 1967

The Above well was plugged as follows:

355' of 8 5/8" surface pipe, cemented with 150 sacks. 3719' of 5 1/2" long
string, cemented with 300 sacks. Plug back T.D. 3645'. Top perferation
3473'. Bottom of the hole was sanded to 3450', and cemented with 20 sacks,
through the dump bailer. 1586' of 5 1/2" long string was recovered from the
hole. Fluid level in the hole was at 340', bridge plug and rock bridge from
340' to 330', and cemented with 25 sacks. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 5/23/67INV. NO. 5272-W