

Form CP-3
Rev. 6-26-62

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1967

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued April 13, 1967.Operator's Full Name Skelly Oil CompanyComplete Address: P. O. Box 649, McCook, Nebraska 69001Lease Name Cunningham "B" Unit Well No. # 4Location C S/2 SE SE Sec. 24 Twp. 27 Rge. 11 (E) (W)WCounty Pratt Total Depth 3510'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 6:00PM Day 26th Month May Year 1967

The Above well was plugged as follows:

369' of 10 3/4" surface pipe, cemented with 175 sacks. 3463' of 5 1/2" long
string, cemented with 400 sacks. This is an open hole. Bottom of the hole
was sanded to 3425', and cemented with 20 sacks, through the dump bailer.
1597' of 5 1/2" long string was recovered from the hole. Fluid in the hole was
bailed down to 300', bridge plug and rock bridge from 300' to 290', and
cemented with 30 sacks. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 5-29-67INV. NO. 5297-W