

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 3

Location S/2 SW SE Sec. 24 Twp. 27 Rge. 11 (E) (W)W

County Pratt Total Depth 3519'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:30PM Day 24th Month May Year 1967

The Above well was plugged as follows:

380' of 10 3/4" surface pipe, cemented with 150 sacks. 3456' of 5 1/2" long
string, cemented with 400 sacks. This is an open hole. Bottom of the hole
was sanded to 3425', and cemented with 20 sacks., through the dump bailer.
1383' of 5 1/2" long string was recovered from the hole. Fluid in the hole was
bailed down to 300', bridge plug and rock bridge from 300' to 290', and
cemented with 30 sacks at 290'. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 15 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-29-67

INV. NO. 5296-w

Signed: Archie Elving
Well Plugging Supervisor