

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21415-00-00
Spot: SENWNW Sec/Twnshp/Rge: 21-12S-21W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BAUGHER C Well #: 2
County: TREGO Total Vertical Depth: 4100 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S MAIN PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3998		150 sx
SURF	8.625	271		175 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2014 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRIAN STOCKMAN Company: BLAKE EXPLORATION Phone: (785) 689-4269

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel and 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 2300', 1720', 950' and 265'. Ran tubing to 3500' and pumped 10 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 2000' and pumped 100 sx cement. Pulled tubing to 1000' and pumped 100 sx cement. Cement circulated out backside. Shut in and pumped an additional 75 sx cement. Cement circulated out braden head. POOH. Topped off w/10 sx cement.

GPS: 38.99848 -099.66503

Perfs:

*10/8/14 - per Ray Dinkel
this a corrected
CP-2/3.
C. Maine*

Remarks: QUALITY CEMENTING TICKET # 342

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

SEP 23 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

SEP 15 2014

Form CP-2/3