

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21358-00-01
Spot: SENWSE Sec/Twnshp/Rge: 23-16S-22W
1714 feet from S Section Line, 1552 feet from E Section Line
Lease Name: SQUIER Well #: 2
County: NESS Total Vertical Depth: 1700 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1483	0	WITH 500 SX CMT
SURF	8.625	237		WITH 175 SX CMT

Well Type: SWD UIC Docket No: D23109.0 Date/Time to Plug: 09/16/2014 2:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: RUN TBG TO BOTTOM & CIRCULATE CMT & HULLS. PULL TBG & TOP OFF & TIE ONTO BACKSIDE AND PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/16/2014 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:


RUN TBG TO 1325' & PUMP 85 SX CMT & 300# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE AND PUMPED 15 SX CMT. PRESSURED UP TO 200# & HELD.

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSC

District: 01

Signed



(TECHNICIAN)

cc: uic
10/8/14 CLKM



Received
KANSAS CORPORATION COMMISSION

OCT 07 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3