

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22787-01-00
Spot: NENESESE Sec/Twnshp/Rge: 24-13S-22W
1200 feet from S Section Line, 200 feet from E Section Line
Lease Name: WINDHOLZ Well #: 1-24H
County: TREGO Total Vertical Depth: 7195 feet

Operator License No.: 34702
Op Name: THE GHK COMPANY, LLC
Address: 6305 WATERFORD BLVD., STE 300
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	4307		790 SX
SURF	9.625	1017		661 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2014 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: WADE KOVASH Company: H2 PLAINS, LLC Phone: (40) 585-8969

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/500 # hulls and 30 sx gel. CIBP at 3500'. Shot perforations at 1600', 1015' and 500'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/12/2014 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' and pumped 30 sx gel followed by 50 sx cement. Pulled tubing to 1617' and pumped 215 sx cement w/300 # hulls. Good circulation of cement. Tied on to backside and squeezed w/30 sx cement. 30 sx in rathole and 10 sx in mousehole.

GPS: 38.90327 -099.70684

Perfs:


No MTD available - Well was never completed as a Horizontal Well, see well comments.

Remarks: ALLIED CEMENT TICKET # 55320

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

OCT 06 2014

CONSERVATION DIVISION
WICHITA, KS

SEP 26 2014

Form CP-2/3