

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20360-00-00
Spot: SESWSW Sec/Twnshp/Rge: 6-16S-42W
319 feet from S Section Line, 4290 feet from E Section Line
Lease Name: CHEEK Well #: 1
County: GREELEY Total Vertical Depth: 5300 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2648		WITH 825 SX CMT
PROD	5.5	5289	0	WITH 100 SX CMT
SURF	8.625	440		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2014 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TRACEY HOLLIS Company: HERMAN L LOEB Phone: (719) 340-8987

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2014 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAK BETWEEN 2648' & 4700'. TOP OF ROD FISH AT 4070'. TOP OF 2 7/8" TBG FISH AT 4732'. PUMP 40 SX CMT WITH 100# HULLS AT 4710' THRU TAPERED STRING OF 2 7/8" & 1 1/2" TBG. FULL CIRCULATION. PUMP 50 SX CMT WITH 150# HULLS AT 2800'. PUMP 30 SX CMT AT 2000'. PUMP 60 SX CMT FROM 500' TO 0'. TOO H W/ TBG. TOP OFF WITH 10 SX CMT. PUMP 40 SX CMT DOWN ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
5100	5114		

Remarks: USED 60/40-POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
SEP 25 2014
KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

10/8/14

OCT 07 2014

CONSERVATION DIVISION

ST

Form CP-2/3