

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20206-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 8-20S-20W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SHIPLEY (MILLER RAY C ET Well #: 1 (1)  
County: PAWNEE Total Vertical Depth: 4345 feet

Operator License No.: 9971  
Op Name: KODIAK PETROLEUM, INC.  
Address: PO BOX 4677  
ENGLEWOOD, CO 80155

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 4240       |             | WITH 2 SX CMT   |
| L1     | 4.5   | 4294       |             | WITH 225 SX CMT |
| PROD   | 5.5   | 4345       | 0           | WITH 150 SX CMT |
| SURF   | 8.625 | 328        |             | WITH 225 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/16/2014 10:30 AM  
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.  
Proposal Rcvd. from: STEVE CRAWFORD Company: KODIAK PETROLEUM Phone: (620) 793-6874

Proposed Plugging Method: SET CIBP ON BOTTOM & 2 SX CMT, THEN PERFORATE AT 1380' & SPOT 50 SX COMMON CMT W/3% CC. WAIT TO SET UP. PERFORATE AT 550' & CIRCULATE CMT TO SURFACE. IF DOES NOT CIRCULATE TIE ONTO BACKSIDE & PUMP 150 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2014 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4240' WITH 2 SXC CMT. PERFORATED AT 1380' & SPOTTED 50 SX COMMON CEMENT W/3% CC. WAITED 1 1/2 HOURS. TAGGED CMT AT 919'. PULLED TBG. PERFORATED AT 550'. PUMPED 15 SX CMT & LOST CIRCULATION. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4296 | 4310 |      |          |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

*ST*

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED

SEP 30 2014

KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

OCT 07 2014

CONSERVATION DIVISION  
WICHITA, KS

10/8/14 CKM

Form CP-2/3