

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-22023-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 5-16S-18W
1980 feet from S Section Line, 330 feet from W Section Line
Lease Name: WERTH Well #: 1-5
County: RUSH Total Vertical Depth: 3753 feet

Operator License No.: 33922
Op Name: MUSTANG ENERGY CORPORATION
Address: PO BOX 1121
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3540		WITH 2 SX CMT
PROD	5.5	3683	1995	WITH 190 SX CMT
SURF	8.625	1203		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2014 9:00 AM
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.
Proposal Rcvd. from: ROD BRIN Company: MUSTANG ENERGY Phone: (785) 623-0533

Proposed Plugging Method: SET CIBP @ 3540' WITH 2 SX CMT. PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2014 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3540' WITH 2 SX CMT. 1ST PLUG AT 1239' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3608	3614		
3591	3595		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

10.8.14 CKM

RECEIVED
SEP 30 2014

KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 07 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3