

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-24250-00-00  
Spot: S2NWSWNW Sec/Twnshp/Rge: 15-8S-18W  
1955 feet from N Section Line, 330 feet from W Section Line  
Lease Name: GISELA ECKART Well #: 2  
County: ROOKS Total Vertical Depth: 1351 feet

Operator License No.: 6037  
Op Name: STAAB OIL CO., A GENERAL PARTNER  
Address: 1607 HOPEWELL RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1350		410 sx
SURF	8.625	215		150

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/26/2014 1:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: FRANK STAAB Company: STAAB OIL CO. Phone: (785) 625-5013

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Perforations: 960' - 1020'  
Well was flowing. Emergency plug with rig over hole.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/26/2014 4:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 943' and pumped 150 sx cement w/350 # hulls to circulate cement to pit area. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 25 sx cement w/700 psi. Shut in pressure 700 psi. 8 5/8" full of cement.

GPS: 39.35900N -099.32400W

Perfs:

Remarks: GLOBAL CEMENTING CO TICKET # 1459

Plugged through: TBG


Received  
KANSAS CORPORATION COMMISSION

OCT 06 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

CM

CC: UIC ✓  
10/8/14 CKM

SEP 29 2014

Form CP-2/3