

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21631-00-00  
Spot: SENEENENW Sec/Twnshp/Rge: 28-16S-16W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: KAISER A Well #: 1  
County: RUSH Total Vertical Depth: 3600 feet

Operator License No.: 32278

Op Name: TENGASCO, INC.

Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3264		
PROD	4.5	3599	0	WITH 200 SX CMT
SURF	8.625	1023		WITH 400 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/17/2014 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: GARY WAGNER

Company: TENGASCO

Phone: (785) 625-6374

Proposed  
Plugging  
Method:

OPERATOR WILL FILL THE HOLE WITH CMT TOP TO BOTTOM. PERFORATE @ 1040'.

Plugging Proposal Received By: ERIC MACLAREN

Witness Type: NONE

Date/Time Plugging Completed: 09/17/2014 1:30 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PERFORATE 2 HOLES @ 1050'. RUN TBG TO 3160' & SPOT 110 SX CMT WITH 200# HULLS. PULL TBG TO 1580' & CIRCULATE 255 SX CMT TO SURFACE UP THE 4 1/2" CASING & ANNULUS FROM 1050' TO SURFACE. TOOH WITH TBG. TOP OFF WITH 5 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3269	3272		
3244	3246		
3211	3214		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP 25 2014

KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

OCT 07 2014

CONSERVATION DIVISION  
WICHITA, KS

10/8/14 CKM



Form CP-2/3