

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20719-00-01
Spot: NWSENW Sec/Twnshp/Rge: 28-26S-12W
3833 feet from S Section Line, 3546 feet from E Section Line
Lease Name: G HOEME Well #: 6
County: PRATT Total Vertical Depth: 3265 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PLACE
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3100		
PROD	5.5	3222	1822	WITH 175 SX CMT
SURF	8.625	428		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/25/2014 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 2790' WITH 2 SX CMT OR SAND TO 2790' WITH 5 SX CMT OR PUMP 200# HULLS WITH 100 SX CMT THROUGH PERFS. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2014 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 2760' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3085	3089		
2844	2852		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed _____

Steve Pfeifer
(TECHNICIAN)

RECEIVED
SEP 30 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 07 2014

CONSERVATION DIVISION
WICHITA, KS

10/8/14 CKM SP

Form CP-2/3