

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 29-27

LOCATION C SW - NE/4

SEC. 13 TWP. 36 RGE. 12-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Haley

Operator Natl. Coop. Ref. Ass. Address 820 Union Natl Bank Bldg - Wichita

Field _____ County Pratt

Total Depth 4201 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 280 ft Circulated with Cement
7" casing at 4200 ft. Plugged back from bottom
to 4150 ft with rock & sand - Dumped 5 sacks cement
at 4150 ft - Shot off & Pulled 3175 ft of 7" casing - Filled
with mud to 280 ft. Bridge & 20 sacks of cement.
Mud to 20 ft. Plug & 10 sacks of cement.
Heb Hebel - Pipe Pulling - Contractor -*

C. M. Stouck
District Conservation Agent

Date 6 - 11 - 48

PLUGGING
FILE SEC. 13 T. 36 R. 12W
BOOK PAGE 29 LINE 27

JUN 14 1948
6-14-48