

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 115-36

LOCATION NE. 22 W. 21 E

SEC. 13 TWP. 26 RGE. 12 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Haley

Operator Ohio Petco. Co. Address Box # 673 - Russell - Kans.

Field \_\_\_\_\_ County Peatt

Total Depth 4155 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 298 ft Circulated with cement.  
7" casing set at 4152 ft. 150 sacks of cement - Plugged  
back to 4140 ft. - Plugged 6 sacks of cement at 4140 ft. Shot  
off & pulled the 7" casing - mud to 298 ft. Set Rock  
Bridge & 20 sacks of cement at 298 ft. mud to 35 ft  
Bridge & 10 sacks of cement at the surface.

Frank Carroll - Plugging Contractor

**PLUGGING**  
FILE SEC 13 TWP 26 R 12 W  
PAGE 115 LINE 36

**RECEIVED**  
CORPORATION COMMISSION  
NOV - 7 - 1951  
CONSERVATION DIVISION  
Wichita, Kansas

C. D. Stough  
District Conservation Agent

Date 11-5-51