

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE NE

SEC. 13 TWP. 26 RGE. 12W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Haynes

Operator J. M. Huber, Co. Inc. Address Box #460, Peatt, Kans.

Field \_\_\_\_\_ County Peatt

Total Depth 4145 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 341 ft. Circulated with cement.  
5 1/2 casing set at 4145 ft. Cemented with 150 sacks cement.  
Lower Well Plug at 3641 ft. Filled hole with gravel  
from 3641 ft to 3590 ft - Dumped 5 sacks of cement at  
3590 ft - Shot off & Pulled the 5 1/2 casing - mud to  
346 ft - Set Rock Bridge & 15 sacks of cement at  
346 ft - Mud to 30 ft Plug & 10 sacks of  
Cement at the surface -

**RECEIVED**  
STATE CORPORATION  
2-28-51  
FEB 28 1951  
**PLUGGING**  
CONSERVATION DIVISION  
Wichita, Kansas  
FILE SEC. 13 TWP. 26 RGE. 12W  
BOOK PAGE 64 LINE 23

C. W. Stoenck  
District Conservation Agent

Date 2-25-51

*F*