

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
SEP 16 1959
7-16-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 63-10 County: Pratt
Location: SW SW SE Sec. 19 Twp. 36 Rge. 13 (E) (W)
Name of Field: _____ Total Depth: 4345

I have this date completed supervision of plugging of:

Lease Name: Hoener Well No. 1
Operator's Full Name: Wayne Walcher
Complete Address: Wichita, Kans
Plugging Contractor: Knight Casing Pulling Co
Address: Great Bend, Kans License No. 436
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3 Day 6 Month Aug Year 1959

The above well was plugged as follows:

*Sample hole to 4100 and dump 5 sack cement with
dump basket. Pull 5 1/2 production pipe. Filled
hole with mud to 350'. Set rock bridge
from 350 to 340'. Dumped 29 sack cement.
Filled hole to 40' with mud. Set rock bridge
from 40 to 50'. Dump cement to base of
collar.*

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE _____
INV. NO. 63-10