

~~15-151-19044-00-01~~

15-151-10944-00-01

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 11 1965  
3-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name R. W. Rine Drilling Co. & (Wayne Walcher)

Complete Address: 420 Union Center, Wichita, Kansas

Lease Name De Werff Well No. # 1

Location SW SW SE Sec. 21 Twp. 26 Rge. 12 (E) (W)W

County Pratt Total Depth 2730'

Abandoned Oil Well Gas Well  Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:30PM Day 9th Month March Year 1965

The Above well was plugged as follows:

452' of 10 3/4" surface pipe, cemented with 350 sacks. 2730' of 5 1/2"  
long string, cemented with 250 sacks. Plug back to 2568'. Top perforation  
2420'. All perforations were squeezed by Halliburton Cementing Co. with  
75 sacks of cement, bringing the top of the cement to 1920' in the hole.  
1100' of 5 1/2" long string was recovered from the hole. Fluid in the hole  
was bailed down to 275', bridge plug set on fluid at 275', and 10' of  
rock bridge, and cemented with 30 sacks. Hole was filled with mud to  
40', and 10' of rock bridge, and cemented with 15 sacks to the base of  
the cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 3/11/65

Signed: Archie Elving  
Well Plugging Supervisor

INV. NO. 499-W