

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 151-20, 669-000 (of this well)

Operator's Full Name W.L. Kirkman, Inc.

Complete Address 453 S. Webb Rd., Box 18611, Wichita, Ks. 67207

Lease Name Johnson Well No. 1

Location NW NW SE Sec. 28 Twp 26S Rge. 12 (E) (W) X

County Pratt Total Depth 3235

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 5:30 Pm. Day 1 Month 8 Year 1980

The above well was plugged as follows:

412' 8 5/8" casing W/325 sax cement. 5 1/2" casing set at 3214' W/175
sax cement. CIBP set at 3058'-Pref's at 2682' to 2686'-Sand back
to 2600'-Top sand W/5 sax mixed cement W/dump bailer. Pull 2198'
casing-Sun mixed & pumped 8 sax hulls-25 sax gel-125 sax 50/50 pos-
W/4% gel & 3% cc to top of casing. Shut in W/200# pressure.

RECEIVED
STATE CORPORATION COMMISSION
AUG - 4 - 80
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 8-5-80
INV. NO. 2755-W