

15-151-10605-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-31-70
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Schusterman Oil Co.

Complete Address 1209 Mid Continent Bldg. Tulsa, OK 74103

Lease Name Simpson Sandstone Unit #5 Well No. 5 (Cooper #2)

Location NE/NW/SE Sec. 28 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4289

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Plug back at 4243 ft.

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour II:00AM Day 28 Month 8 Year 1970

The above well was plugged as follows:

735 ft of 8 5/8 surface pipe cemented with 425 sacks. 4272 ft of
4 1/2 long string cemented with 250 sacks. Top perf. 4194 ft. Sand
back to 4180 ft, 4 sacks cement with bailer. Pulled 2428 ft of 4 1/2.
Set 10 ft rock bridge at 350 ft. Fill hole with 5 yds of redimix
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell Biberstein
Well Plugging Supervisor

DATE 9/1/70
INV. NO. 2460-W