

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Schusterman Oil Company

Complete Address 1209 Mid-Continent Bldg. Tulsa, OK 74103

Lease Name Simpson Sandstone Unit #3 Well No. 3 (Hall #1)

Location SW/SW/NE Sec. 28 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4270

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 10:00 AM Day 24 Month 8 Year 1970

The above well was plugged as follows:

904 ft of 8 5/8 surface pipe cemented with 300 sacks. 4294 ft of  
5 1/2 long string cemented with 100 sacks. Top perf. 4204 ft. Sand  
back to 4180 ft, 5 sacks with bailer. Pulled 3526 ft of 5 1/2. Set  
10 ft rock bridge at 350 ft. Fill hole with 5 yds redimix to base  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

AUG 26 1970  
CONSERVATION DIVISION

Wichita, Kansas  
8-26-70

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/26/70

INV. NO. 2435-W