

KANSAS

Form CP-3  
Rev. 6-4-68

*4*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
9-28-70  
SEP 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Schusterman Oil Co.

Complete Address 1209 Mid-Continent Bldg. Tulsa, OK

Lease Name Simpson Sandstone Unit #7 Cooper #1 Well No. 7

Location SW/NW/SE Sec. 28 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4248

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 12:30 PM Day 25 Month 9 Year 1970

The above well was plugged as follows:

825 ft of 8 5/8 surface pipe cemented with 400 sacks. 4296 ft of  
4 1/2 long string cemented with 700 sacks. Top Perf. 4248 ft. Sand  
back to 4200 ft, 4 sacks cement with bailer. Pulled 1804 ft of 4 1/2.  
Set 20 ft rock bridge at 350 ft. Fill hole with 5 yds redimix to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-28-70

INV. NO. 2591-W

Signed: [Signature]  
Well Plugging Supervisor