

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Champlin Petroleum Co.

Complete Address Box 308 Ellinwood, Ks

Lease Name Baird Well No. 2

Location SE/NE/SE Sec. 27 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 5282

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 9:00 AM Day 19 Month 10 Year 1971

The above well was plugged as follows:

480 ft 10 3/4 surface pipe cemented with 250 sacks. 5025 ft 5 1/2 long  
string cemented with 150 sacks. Top perf. 4952 ft. Set plug at 4900  
ft, 5 sacks cement with bailer. Pulled 4090 ft 5 1/2. Set 20 ft rock  
bridge at 250 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 10/20/71  
INV. NO. 4514-W