

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-119-20.855-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

8/97

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE FOX "G" WELL# 1 SEC. 13 T. 32S R. 30 (XXXX/West)

C - S/2 - SW - SE SPOT LOCATION/QQQQ COUNTY MEADE

330 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1621' CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 5754' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 5609'-5630' (SQZD), 5655'-5669'

ELEVATION 2725' / -- T.D. 6100' PBSD 5752' ANHYDRITE DEPTH 1622'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS. TIH W/TBG. TO PBSD. LOAD HOLE W/9 PPG MUD AND ESTABLISH CIRCULATION DOWN TBG. MIX AND SPOT 2 SXS HULLS AND 20 SXS CLASS H CEMENT (YIELD 1.06 CU. FT./SK) FROM 5630'-5530'. PULL FREE POINT AND CUT OFF 5-1/2" CSG. SPOT 40 SXS CMT @ CUT-OFF DEPTH. SPOT 40 SXS CMT @ 1671-1571'. SPOT 40 SXS CMT @ 650-550'. SPOT 20 SXS CMT @ 53-3'. CUT OFF 8-5/8" CSG 3' BELOW GROUND LEVEL AND CAP. INSCRIBE CAP. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MR. JERRY RUTTMAN PHONE# (316) 629-4382

ADDRESS P.O. BOX 351 City/State LIBERAL, KANSAS 67905-0351

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/30/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (Signature)
DIVISION PRODUCTION ENGINEER

KANSAS STATE CORPORATION COMMISSION
197 JAN 31
12:35 PM

1/98



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 3, 1997

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Fox "G" #1
API 15-119-20,855-0001
330 FSL 1980 FEL.
Sec. 13-32S-30W
Meade County

Dear Mr. Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

ANADARKO PETROLEUM CORPORATION

PHONE 316 - 624 - 6253 • 1701 NORTH KANSAS AVE. • P.O. BOX 351 • LIBERAL, KANSAS 67905 - 0351



January 30, 1997

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm. 2078
Wichita, Kansas 67202

Attn: Mr. Jeff Klock

Re: Well Plugging Application Form (Form CP-1)

Fox "G" No. 1
Section 13-32S-30W
Meade County, Kansas

RECEIVED
KANSAS CORP COM
1997 JAN 31 P 12:55

Dear Jeff:

Enclosed in duplicate is a well plugging application (KCC Form CP-1) for the referenced well. Upon approval of this application, please notify this office at the letterhead address so that plugging operations may commence.

Very truly yours,

A handwritten signature in cursive script that reads "John A. Broman".

John A. Broman
Division Production Engineer
JMD/sh

Enclosure

cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
WI Owners

kccintpa.doc