

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-151-21416-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corp KCC LICENSE # 5506  
(owner/company name) (operator's)

ADDRESS 125 N. Market, Suite 1000 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (620) 886-5605

LEASE Swisher WELL# B-1 SEC. 29 T. 27 R. 11 (East/West)

S/2 - NE - NW - SPOT LOCATION/QQQQ COUNTY Pratt

990 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL \_\_\_ GAS WELL X D&A \_\_\_ SWD/ENHR WELL \_\_\_ DOCKET# \_\_\_

CONDUCTOR CASING SIZE \_\_\_ SET AT \_\_\_ CEMENTED WITH \_\_\_ SACKS

SURFACE CASING SIZE 13 3/8" SET AT 250' CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4562' CEMENTED WITH 250 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4313' to 4321', 4326' to 4332'

ELEVATION 1807 T.D. 4565 PBDT 45 ANHYDRITE DEPTH \_\_\_  
(G.L. (K.B.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR \_\_\_ CASING LEAK \_\_\_ JUNK IN HOLE \_\_\_

PROPOSED METHOD OF PLUGGING Spotsand 50' Above Perfs @ 4260. Place 2 sax on top with bailer. Cut casing & spotplugs as follows: 50 sax @ 530', 50 sax @ 280', & 10 sax @ 40'. Fill to surface.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? \_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W Durr PHONE# 620 886-5606 Ext 27

ADDRESS 1966 Rodeo Dr, P.O. Box 168 City/State Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Clarke Corp. KCC LICENSE # 5160 5105

(company name) (contractor's)  
ADDRESS 107 W. Fowler, Medicine Lodge, KS 67104 PHONE # (620) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) \_\_\_

PAYMENT OF THE PLUGGING FEE (K.S.A. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/26/02 AUTHORIZED OPERATOR/AGENT: Carl W. Durr  
(signature)

FEB 27 2002

CONSERVATION DIVISION



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Woolsey Petroleum Corporation  
125 N. Market, Suite 1000  
Wichita, KS 67202-1775

March 04, 2002

Re: SWISHER #1-B  
API 15-151-21416-00-00  
NWSHENW 29-27S-11W, 990 FNL 1980 FWL  
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely,

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor