

4-032024

11-16

API number: 15-051-30219-0000 1965

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SW /4 SEC. 28 , 15 S, 20 W
990 feet from S section line
4290 feet from E section line

Operator license# 5146 Lease A. North well # 2

Operator: Rains & Williamson Oil Co., Inc. County Ellis

Address: 220 W. Douglas Well total depth 3965 feet
Suite #435 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 221 feet

128,86

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 16 Month: November Year: 94

Plugging proposal received from: A.D. Belt

Company: Rains & Williamson Oil Co., Inc. Phone:

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 300# hulls - 15 sxs.gel.

RECEIVED
STATE CORPORATION COMMISSION
DEC 08 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 9:10A.M., Day: 16, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 221' w/150 sxs. 5 1/2" set @ 3963'
w/150 sxs. D.V. @ 1500'- to surface w/500 sxs. 2' O.H.
Down 5 1/2" casing 50 sxs. cement blend w/200# hulls mixed in, followed
with 15 sxs gel with 100# hulls mixed in, followed with 175 sxs.
cement blend to Max. P.S.I. 1250#. Close in P.S.I. 1250#. Tested
8 5/8" to 300# cement at surface. Plug complete.

Remarks:
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC X, NO Dakota plug:YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did observe the plugging. Carl Goodrow

INVOICED

DATE 12-9-94

INV. NO. 41827

(agent)

Form CP-2/3

11-16 JAN 19 1995 FEB 02 1995