

4-032025

11-16

051 30358-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1966

SE NE SW /4 SEC. 28 , 15 S, 20 W  
1650 feet from S section line  
2970 feet from E section line

Operator license# 5146 Lease A. North well # 5

Operator: Rains & Williamson Oil Co., Inc. County Ellis 12968

Address: 220 W. Douglas Well total depth 3990 feet  
Suite #435 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 239 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Halliburton Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 16 Month: November Year: 94

Plugging proposal received from: A.D. Belt

Company: Rains & Williamson Oil Co., Inc. Phone:     

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 300# hulls - 15 sxs.gel.

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 08 1994  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 10:30A.M., Day: 16, Month: November, Year: 94

Actual plugging report: 8 5/8" set @ 239' w/175 sxs. 5 1/2" set @ 3988'  
w/150 sxs. D.V. @ 1550'- to surface w/500 sxs. 2' O.H.  
Down 5 1/2" casing 50 sxs. cement blend w/200# hulls mixed in, followed  
with 15 sxs gel with 100# hulls mixed in, followed with 200 sxs.  
cement blend to Max. P.S.I. 1200#. Close in P.S.I. 0#. w/ cement at  
surface. Cement at surface in 8 5/8" tested to 300# P.S.I.  
Plug complete.

Remarks:       
Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL     

I      [      ] observe the plugging. Carl Goodrow

**INVOICED**  
DATE 12-9-94  
INV. NO. 41878

(agent)  
Form CP-2/3

11-16 JAN 19 1995 FEB 02 1995