

4-020112

15-051-30293-0000

Docket #D-13,041

API number: 15- - (09-09-1996)

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-2

SE NW SE /4 SEC. 28 , 15 S, 20 W
1650 feet from S section line
1650 feet from E section line

Operator license# 05146

Lease: A. North Well # 6

Operator: Rains & Williamson Oil Co., Inc.
Address: 220 W. Douglas
Suite 435
Wichita, Kansas 67202

County: Ellis 135.85
Well total depth 4180 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 209 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD X _____, D & A _____

Plugging contractor: Rains & Williamson Oil Co., Inc. License# 05146

Address: 220 W. Douglas, Suite 435, Wichita KS 67202

Company to plug at: Hour: _____ Day: 02 Month: October Year: 1996

Plugging proposal received from: A. D. Belt

Company: Rains & Williamson Oil Co., Inc. Phone: 316 793 6656

Were: 8 5/8" Surface casing set @ 209' w/165 sx cmt; 5 1/2" production casing set @ 4161' w/400 sx cmt; (2 staged 1540' to surf.); Elevation: 2272'; TD: 4180'; PBD: 4180'; Anhydrite Depth: 1495 - 1540'; Open Hole 4161 - 4180;

Order 185 sx 60/40 pozmix 10% gel cement w/500#s hulls and 21 sx gel

Plugging Proposal Received by: Herb Deines / Ken Kuhn

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:15 AM Day: 02 Month: October Year: 1996

Actual plugging report: Tied onto top of production casing and pumped 75 sx cmt w/500# hulls; Followed w/21 sx gel spacer; Followed with 110 sx cmt; Maximum pressure: 750 #s; Static/End pressure: 310 #s; Completion Time: 10:15 AM

Remarks: Halliburton performed the plug job.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X NO _____

Plugged through TUBING _____, CASING X Elevation: 2272 KB GL

I hereby certify that I have observed the plugging.

Ken Kuhn
(agent)

RECEIVED
KANSAS CORPORATION COMMISSION
OCT - 11 P 12:14

10-04-97

INVOICED

DATE 10-9-96

INV. NO. 46671

10-2