

041177

5-29

238  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

D-15,921  
API NUMBER 15-051-20682-0000  
SE SW SW SEC. 8, T 11 S, R 20 W/E

330 feet from S section line  
4920 feet from E section line

Lease Name Fischer Well # A-2  
County Ellis 121.29

Well Total Depth 3732 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 220 w/150 sks cement

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3474  
Elada Oil Co.

Operator: \_\_\_\_\_  
Name: \_\_\_\_\_  
Address: Box 7  
Palco, Ks. 67657

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_  
Allied Cement

Plugging Contractor \_\_\_\_\_ License Number \_\_\_\_\_  
Address: Plainville, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: May Year: 19 90

Plugging proposal received from Ken Bruna

(company name) Plainville Oil Well Serv. (phone) \_\_\_\_\_

were: 5 1/2 casing set at 3680 w/150 sks cement: perfs at 3354.  
O.H. to 3732'. D.V. at 1480 w/325 sks. Ordered 350 sks 65/35 poz 10% gel  
w/1/4" f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:20PM Day: 29 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/65 sks cement w/1/4" f.c. plus  
pumped in add 250 sks cement w/1/4" f.c. and 4 sks hulls mixed in cement.

Max 750# S.I. 500#. Pumped in 8 5/8" casing w/75 sks cement w/1/4" f.c. and  
1 sks hulls mixed in cement. Max 500# S.I. 300#.

JUN 04 1990

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: dual completed  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-12-90  
INV. NO. 28398  
5-29

G.L.S.

Signed Dennis L. Hamel (TECHNICIAN)  
Dennis L. Hamel