

To: 1 061127  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-9-88  
API NUMBER 15- 151-21,777-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Operator: General Oil Company, Inc.  
Name & Address 1540 North Broadway, Suite 202  
Wichita, KS 67214

NW NW SW, SEC. 2, T 27 S, R 12 W  
2310 feet from S section line  
4950 feet from E section line

Lease Name Haas Well # 1  
County Pratt 149.01  
Well Total Depth 4585 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 408

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 9 Year: 1988

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4532' Perfs at 4152-92'

1st plug pump 30 sx cement, stop plug, at 4000'

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper  
plug and pump 160 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 p.m. Day: 9 Month: 8 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement, stopped plug at 4000',  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released  
wiper plug  
10 3/4" and pumped 160 sx cement.

Maximum pressure 500 psi and shut in 200 psi. Recovered 2024' of 4 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 8-16-88

INV. NO. 21851