

To: 1 040623 2-13
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,944 -00-00 103
NW NW SW, SEC. 2, T. 27 S, R. 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9582

Operator: Studer Oil Company, Inc.
Name & Address P.O. Box 925
Pratt, KS 67124

2310 feet from S section line

4950 feet from E section line

Lease Name Haas Well # 2

County Pratt 149.82

Well Total Depth 4610 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 385

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 2 Year: 1992

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4567' w/175 sx cement, Perfs at 4146-76'

1st plug set CIBP at 4100' and dump 2 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 a.m. Day: 13 Month: 2 Year: 1992

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' and dumped 2 sx cement on top of CIBP through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement;

10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2018' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

DATE 2-27-92

WV. NO. 34662

Signed Steve Pfeifer
(TECHNICIAN)