

1 060877

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9514  
Operator: D & D Production, Inc.  
Name & Address: 403 S. Main, P.O. Box 321  
Pratt, KS 67124

API NUMBER 15-151-21,802-00-00  
S NE NW, SEC. 3, T 27 S, R 12 W/EX  
4120 feet from S section line  
3300 feet from E section line

Lease Name Lathrop Well # A-7  
County Pratt 143-98  
Well Total Depth 4430 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co., Inc. License Number 5929  
Address 620 Hubbard, Box 823, Great Bend, KS 67530

Company to plug at: Hour: 2:20 a.m. Day: 24 Month: 9 Year: 19 86

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling (phone) 316-792-1171  
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1899' GA  
Anhydrite 691'

- 1st plug at base anhydrite with 50 sx cement
- 2nd plug below surface pipe with 40 sx cement
- 3rd plug at 40-0' with 10 sx cement
- 4th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:15 a.m. Day: 24 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement

- 2nd plug at 330' with 40 sx cement
- 3rd plug at 40' with 10 sx cement
- 4th plug to circulate rathole with 15 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

SEP 25 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED  
DATE 9-25-86  
INV. NO. 15016

Signed Paul A. Luthi  
(TECHNICIAN)