

1 030709

225R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,793 -00-00

Approx C W/2, SEC. 3, T. 27 S, R. 12 (W)X

2510 feet from S section line

3930 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9514

Lease Name Lathrop Well # A-6

Operator: D & D Production, Inc.

County Pratt 146 25

Name & Address 403 South Main, Box 321

Well Total Depth 4500 Viola feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address P. O. Box 823, Great Bend, KS 67530

Company to plug at: Hour: 1:00 pm Day: 25 Month: June Year: 19 86

Plugging proposal received from Larry Curtis

(company name) Duke (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1019

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 40 sx cement

3rd plug from 40' to surface with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 pm Day: 25 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement, 2nd plug at 330' with 40' sx cement, 3rd plug from 40' to surface with 10 sx cement, 4th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging STATE CORPORATION COMMISSION

Signed Steve Durrant (TECHNICIAN)

DATE JUL 10 1986

JUL - 8 1986

INV. NO. 14315

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84