

To: 1 010101
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-26,649 - 00-00

C NE NW, SEC. 3, T 27 S, R 12 WEX

4620 feet from S section line

3300 feet from E section line

Lease Name Lathrop Well # A-3

County Pratt

Well Total Depth 4640 150' 8" feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 357

TECHNICIAN'S PLUGGING REPORT

Operator License # 9514

Operator: D & D Production, Inc.

Name & Address P. O. Box 321

Pratt, KS 67124

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:20 pm Day: 3 Month: March Year: 19 86

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4500' PBDT 4250' Perfs at 4352-82' Plug at 4250', 4223-25'

1st plug sand back to 4170' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:50 pm Day: 3 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 0

Remarks: Recovered 1900' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 12 1986

INV. NO. 12918

RECEIVED STATE CORPORATION COMMISSION

MAR 11 1986

CONSERVATION DIVISION Wichita, Kansas

Signed [Signature] (TECHNICIAN)