

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21096-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 6-32S-35W
4021 feet from S Section Line, 3904 feet from E Section Line
Lease Name: BROWNELL Well #: 1-3
County: STEVENS Total Vertical Depth: 2835 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2835	0	WITH 443 SX CMT
SURF	8.625	629		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2014 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PLUGGED PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 09/03/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAG FILL AT 1817'. SPOT 100 SX CMT TO 830'. TBG STUCK IN HOLE. CUT TBG AT 764'. TOC INSIDE TBG AT 790'. 1ST PLUG AT 764' WITH 80 SX CMT TO 0'. 2ND PLUG CHECK BACKSIDE TO 300 PSI WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2782	2805		
2729	2761		
2680	2712		
2629	2656		
2600	2664		

Received
KANSAS CORPORATION COMMISSION
SEP 26 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
10/1/14 CKM

(TECHNICIAN)

Form CP-2/3