

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21416-00-00
Spot: S2NENW Sec/Twnshp/Rge: 29-27S-11W
990 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: SWISHER Well Number: 1-B
County: PRATT Total Vertical Depth: 4565 feet

Operator License No.: 5506 Conductor Pipe: Size _____ feet: \$148.36
Op Name: WOOLSEY PETROLEUM CORPORATION Surface Casing: Size 13.375 feet: 250 WITH 150 SX CMT
Address: 125 N. MARKET, SUITE 1000 Production: Size 5.5 feet: 4562 WITH 250 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/15/2002 9:15 AM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: SHAWN TILLOTSON Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: CIBP @ 4250' & 2 SX CMT ON TOP. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 280' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/15/2002 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4313-4321' & 4326-4332'. SET CIBP @ 4250' & PUT 2 SX CMT ON TOP OF CIBP. LAID DOWN CASING. RUN TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1729' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE March 28-02

INV. NO. 2002061577

RECEIVED

MAR 28 2002

KCC WICHITA

MAR 18 2002

NP

Form CP-273