

1 040832

3-16

API NUMBER 15-151-22,116-00-06

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 NE SE, SEC. 26, T 27 S, R 11 W/X
1650 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30128

Lease Name Freund Well # 1

Operator: Kenneth S. White

County Pratt

Name & Address: 200 E. 1st, Ste. 210.

Well Total Depth 4290 139.42 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Co., Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 16 Month: 3 Year: 19 94

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Co., Inc. (phone) 316-793-5742

Work: to fill hole with heavy mud and spot cement through drillpipe

1st plug at 600' with 50 sx cement, 2nd plug at 280' with 40 sx cement.

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:15 a.m. Day: 16 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 4280' with 90' sx cement,

2nd plug at 600' with 50 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 22 1994

Remarks: Used 50/50 Pozmix 2% gel 18% salt 10% Gelsonite by Allied.

(If additional description is necessary, use BACK of this report)

observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

INVOICED

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE MAR 29 1994

INV. NO. 40181