

1 120828

9-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,841-00-01

N/2 NE SW, SEC. 26, T. 27 S, R. 11 W/X

2310 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3180

Lease Name Sitton Well # 1-26 OWVO

Operator: Deutsch Oil Company

County Pratt 135.78

Name: Address 107 N. Market, Ste. 1115

Well Total Depth 4178 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor DS&W Well Servicing Co. Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2:30 p.m. Day: 20 Month: 9 Year: 19 93

Plugging proposal received from Kent Deutsch

(company name) Deutsch Oil Company (phone) 316-267-7551

were: 4 1/2" at 4178' w/125 sx cement, Perfs at 3990-4010'
1st plug sand back to 50' above perforations and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100.sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 20 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3940' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-700 psi and shut in 200 psi.

RECEIVED STATE CORPORATION COMMISSION

SEP 29 1993

CONSERVATION DIVISION Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1675' of 4 1/2" casing.

INVOICED

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 10-4-93 BY NO 38846 9-20

Signed Duane Rankin (TECHNICIAN)