

020083

JUN 23 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,841-00-00

N/2 NE SW, SEC. 26, T 27 S, R 11 W/E  
2310 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3180

Lease Name Sitton Well # 1

Operator: Deutch Oil Company  
Name & Address: 107 North Market, Suite 1008  
Wichita, KS 67202

County Pratt 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 300

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 23 Month: 6 Year: 19 87

Plugging proposal received from Larry Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 541-560'  
1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 330' with 50 sx cement,  
3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:35 p.m. Day: 23 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 4400' with 80 sx cement,

2nd plug at 560' with 50 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 30 1987

CONSERVATION DIVISION Wichita Kansas

Remarks: Used 60/40 Pozmix 4% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

DATE 7-1-87

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 17384