

1 080259

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,032-0000

SE SE NW , SEC. 13 , T 26 S, R 12 W/E

2970 feet from N SE Corner of XXX section line

2970 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Rundell Well # 1-13

Operator: Texas Energies, Inc.

County Pratt 141.70

Name & Address P. O. Box 947

Well Total Depth 4360 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 14 Month: November Year: 19 84

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4181' PBTD 3500' Perfs from 4004 - 3431' Lock Set Plug at 3695'

1st plug sand back to 3375' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 14 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4181' PBTD 3500' Perfs from 3431-4004' Lock set plug

at 3695'

1st plug sanded back to 3375' and dumped 4 sx cement on top of sand through

bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

NOV 21 1984

11-21-84
CONSERVATION DIVISION

Wichita, Kansas

Maximum pressure 300 psi and shut in pressure 100 psi

Remarks: Recovered 2900' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If desired, please observe this plugging.)

DATE 12-4-84

INV. NO. 5785

Signed J. H. Metz (TECHNICIAN)