

7-21

To: 1 040299  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-20,645-0000  
C SW SW, SEC. 13, T. 26 S, R 12 W/E  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5585  
Operator: Clinton Production, Inc.  
Name & Address: 330 North Armour  
Wichita, KS 67206

Lease Name Schwertfeger Well # 1  
County Pratt 133.71  
Well Total Depth 4114 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635  
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 21 Month: 7 Year: 19 89

Plugging proposal received from Richard McIntyre  
(company name) Great Bend Casing Pullers (phone) 316-793-9711  
were: 5 1/2" at 4114' PBTD 3080' Perfs at 3009-16'

1st plug sand back to 2950' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement:

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p. Day: 21 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2959' and dumped 5 sx cement on top of  
sand bridge with bailer,  
2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. STATE CORPORATION COMMISSION  
Maximum pressure 600 psi and shut in 250 psi.

RECEIVED  
JUL 31 1989  
7-31-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2100' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-1-89  
INV. NO. 25469

Signed Stephen J. Pfeifer  
(TECHNICIAN)