

7-21

To: 1 040298  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,826-0000  
C. NW SE, SEC. 13, T. 26 S, R. 12 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5585  
Operator: Clinton Production, Inc.  
Name & Address: 330 North Armour  
Wichita, KS 67206

Lease Name Miskimen Well # 1  
County Pratt 143.00  
Well Total Depth 4400 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 21 Month: 7 Year: 19 89

Plugging proposal received from Richard McIntyre

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 4 1/2" Packer at 3673' Perfs at 3643-51, 3888-94, 3901-08, 3772-76'

1st plug sand back to 3521' and dump 4 sx cement on top of sand bridge with bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 21 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3521' and dumped 4 sx cement on top of  
sand bridge with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
7-31-89  
JUL 31 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2037' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 8-1-89

INV. NO. 25468

Signed Steve Pfeifer  
(TECHNICIAN)