

1 010031

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,002 -0000

SW SW NE, SEC. 13, T 26 S, R 12 W/X

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5601

Lease Name Fisher Well # 1

Operator: Associated Petroleum Consultants, Inc. County Pratt 130.16

Name & Address 600 One Main Place

Well Total Depth 4005 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:00 am Day: 4 Month: September Year: 19 85

Plugging proposal received from Dick Armer

(company name) Associated Petroleum Consultants, Inc. (phone) 316-672-9383

were: 4 1/2" at 4309' Perfs at 3880-3893-3619 Anhydrite top at 685' Fluid level at 800'

1st plug sand back to 3570' and dump 4 sx cement on top of sand through bailer
or squeeze with 50 sx cement at 3500'

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sack hulls

release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:40 am Day: 4 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement at 3500', 2nd plug squeezed well with
10 sx gel, 50 sx cement, 7 sx gel, and 125 sx cement.

Maximum pressure 100 psi and shut in 0

Remarks: Recovered 2460' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE SEP 17 1985

INV. NO. 10104

9-4

SEP 16 1985

7-16-85

CONSERVATION DIVISION
Wichita, Kansas

Signed

(TECHNICIAN)

FORM CP-2/3
Rev. 01-84