

1 060823

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,582-0000  
NW NE NW, SEC. 18, T 26 S, R 12 W/3

4950 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5313

Lease Name Schiewe "B" Well # 1  
County Pratt

Operator: F & M Oil Company  
Name & Address 422 Union Center  
Wichita, KS 67202

Well Total Depth 4445 144.46 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 6 Month: March Year: 19 86

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4445' PBD 4354' Perfs at 3164, 3168, 3172 & 3178'

1st plug sand back to 3100' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls  
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 16 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3100' and dumped 4 sx cement on top of  
sand through bailer. 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi

Remarks: Recovered 2000' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 10 1986

INV. NO. 12882

STATE CORPORATION COMMISSION signed Paul A. Luthi  
(TECHNICIAN)

MAR 10 1986  
3-10-86  
CONSERVATION DIVISION