

1 120337

11-7

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,841-0000

C SW SW, SEC. 23, T 26 S, R 12 W ~~XX~~  
660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Trinkle Well # 1

Operator: McCoy Petroleum Corporation  
Name &  
Address 110 South Main, Suite 500  
Wichita, KS 67202

County Pratt 145.44

Well Total Depth 4475 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 437

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hayes Well Service License Number 5429

Address Attica, KS

Company to plug at: Hour: 10 a.m. Day: 7 Month: 11 Year: 19 89

Plugging proposal received from Daryl Hanson

(company name) McCoy Petroleum Corporation (phone) 316-532-5452

were: 4 1/2" at 4473' PBSD 4250' Perfs at 3902-4309' (3 sets)

1st plug set CIBP at 3850' with 3 sx cement on top,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 7 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3850' inside 4 1/2" casing,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Pumping pressure 0-400 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1989

11-14-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If needed) observe this plugging.

DATE NOV 16 1989

Signed Dan Goodrow  
(TECHNICIAN)

INV. NO. 26478  
11-7