

1 010026

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,409-0001
C NE NE , SEC. 23 , T 26 S, R 12 W XX
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5069
Operator: Argonaut Energy Corporation
Name & Address: P. O. Box 4060
Amarillo, TX 79116-4060

Lease Name Block Well # 1
County Pratt 143.00
Well Total Depth 4400 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8" feet 384

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:45 am Day: 27 Month: August Year: 19 85

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" mats 4399.5' PBD 4364' Perfs at 3910-4354'
1st plug sand back to 3860' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 11:30 am Day: 27 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3860' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pump 130 sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2620' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE SEP 10 1985
INV. NO. 9944

Signed Paul A. Luthi (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 7-6-85

SEP 6 1985

CONSERVATION DIVISION Wichita, Kansas

15-151-20489-00-01



GAMMA-GUARD FORXO LOG

COMPANY ARGONAUT ENERGY CORPORATION WELL BLOCK #1 FIELD PRATT State KANS.	COMPANY ARGONAUT ENERGY CORPORATION WELL BLOCK #1 FIELD COUNTY PRATT STATE KANSAS Location STATE CORPORATION COMMISSION Sec. 23 Twp. 26S NE-NE MAY 15 1985 5-15-85 CONSERVATION DIVISION Wichita, Kansas
Other Services: CAVL FF-MSG	
Permanent Datum GROUND LEVEL Elev. 1874' Log Measured From KELLY BUSHING Ft. Above Perm. Datum Drilling Measured From KELLY BUSHING	
Elev.: K.B. 1881' D.F. G.L. 1874'	
Date	9-3-77
Run No.	ONE
Depth—Driller	4400'
Depth—Welex	4401'
Btm. Log Inter.	4393'
Top Log Inter.	380'
Casing—Driller	8-5/8" 384 @ @ @
Casing—Welex	8-5/8" 380
Bit Size	7-7/8"
Type Fluid in Hole	SALT GEL.
Dens. Visc.	9.7 156
pH Fluid Loss	6.8 18.0 ml ml ml ml
Source of Sample	FLOW LINE
R _m @ Meas. Temp.	.203 @ 98 °F @ °F @ °F
R _{ml} @ Meas. Temp.	.12 @ 98 °F @ °F @ °F
R _{mc} @ Meas. Temp.	.66 @ 98 °F @ °F @ °F
Source R _m R _{ml}	MEASURED
R _m @ BHT	.165 @ 115 °F @ °F @ °F
Time Since Circ.	6 HOURS
Max. Rec. Temp.	115°F @ T.D. °F @ °F @ °F
Equip. Location	9431 GREAT BEND
Recorded By	J. EARLY
Witnessed By	MR. DeOTTE