

4-17

To: 1 040265
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,765-0000
NE NW , SEC. 24 , T 26 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5585
Operator: Clinton Production Inc.
Name & Address: 330 North Armour
Wichita, KS 67206

4620 feet from S section line
3300 feet from E section line
Lease Name Gatz Well # 1
County Pratt
Well Total Depth 4400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

143.00

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 4 Year: 19 89

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4402' PBD 4130' Perfs at 3886-3902'
1st plug sand back to 3835' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 17 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3830' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in 50 psi.

APR 19 1989 4-17-89

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1740' of 4 1/2" casing. (If additional description is necessary, use BACK of this for Wichita, Kansas)

INVOICED

DATE 4-24-89 INV. NO. 24465

Signed Stephen J. Tupper (TECHNICIAN)

15-151-20765-0000



COMPENSATED ACOUSTIC VELOCITY LOG

COMPANY ARGONAUT ENERGY CORPORATION WELL #1 GATZ FIELD LELA County PRATT State KANSAS	COMPANY ARGONAUT ENERGY CORPORATION WELL #1 GATZ FIELD LELA COUNTY PRATT STATE KANSAS Location C-NE-NW Sec. 24 Twp. 26S Rge. 12W Other Services: GAMMA-GRD-SWN			
Permanent Datum GROUND LEVEL Elev. _____ Elev.: K.B. _____ Log Measured From KELLY BUSHING Ft. Above Perm. Datum D.F. _____ Drilling Measured From KELLY BUSHING G.L. _____				
Date	6-14-80	6-14-80		
Run No.	ONE	VELOCITY	GAMMA	
Depth—Driller	4400'	4400'		
Depth—Welex	4401'	4401'		
Btm. Log Inter.	4398'	4378'		
Top Log Inter.	396'	396'		
Casing—Driller	8-5/8" @ 400'	@	@	@
Casing—Welex	8-5/8" @ 396'			
Bit Size	7-7/8"			
Type Fluid in Hole	DRILLING MUD			
Dens. Visc.	9.4 147			
pH Fluid Loss	7.5 12.4 ml			
Source of Sample	FLOW LINE			
R _{ml} @ Meas. Temp.	.48 @ 72 °F			
R _{ml} @ Meas. Temp.	.12 @ 76 °F			
R _{ml} @ Meas. Temp.	.22 @ 74 °F			
Source R _{ml} R _{ml}	MEASURED			
R _{ml} @ BHT	.32 @ 116 °F	@ °F	@ °F	@ °F
Time Since Circ.	3 HOURS			
Max. Rec. Temp.	116 °F @ T.D.	°F @	°F @	°F @
Equip. Location	702 GREAT BEND			
Recorded By	M. SCHRADER			
Witnessed By	MR. DEOTTE			

RECEIVED
 STATE CORPORATION COMMISSION
 5-15-85
 MAY 15 1985
 CONSERVATION DIVISION
 Wichita, Kansas

END HERE