

To: 1 120827
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-20

API NUMBER 15-151-22,000-0000
NW NW SE, SEC. 24, T. 26 S, R. 12 W/X
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3180 & 30224
Operator: Deutsch Oil Co./Dominion Oil Co.
Name:
Address 107 N. Market, Ste. 1115
Wichita, KS 67202

Lease Name Howell Well # 1-24
County Pratt 136.50
Well Total Depth -4200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing Co. Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:45 a.m. Day: 20 Month: 9 Year: 1993

Plugging proposal received from Kent Deutsch
(company name) Deutsch Oil Co. (phone) 816-267-7551

were: 4 1/2" at 4194' w/125' sx cement. Perfs at 4060-96'
1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12 p.m. Day: 20 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4010' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 100 sx cement.
Pumping pressure 0-500 psi and shut in 250 psi.

STATE CORPORATION COMMISSION

SEP 29 1993
7-29-93
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2225' of 4 1/2" casing.
(Additional description is necessary, use BACK of this form.)

(1) d / (XXXXXX) observe this plugging.

INVOICED
DATE 10-4-93
NO. 38844
9-20

Signed Duane Rankin
(TECHNICIAN)